

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 10/02/18.

CORNER DESIGNATION: N-3, The South 1/4 corner of Section 18, Township 4 North, Range 33 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Odell and Lewis, Deputy Surveyors, under Contract No. 110, dated February 7, 1865. Notes state:

Set 1/4 Sec. post. Drove charred stake. Dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Reestablished corner point at the intersection of centerline of Koebcke Road (East-West) with a field berm extending South.

MONUMENT MARKING DETAIL:

T4N R33E
S18
1/4 -----
S19
2018
PLS 1106

MONUMENT SET: Set a 2" aluminum cap on 5/8 by 24" rebar with aluminum cap 8" below road surface for corner. Cap marked as shown in Monument Marking Detail.

New accessories:

A brass washer stamped "PLS 1106", nailed to the East side of a railroad tie post, 1 foot above ground bears S 02° W, 11.2'.

A 5/8" by 24" rebar with red plastic cap bears S 02° W, 32.2'.

A 5/8" by 24" rebar with red plastic cap bears S 35° E, 19.5'.

A 5/8" by 24" rebar with red plastic cap bears S 25° W, 15.9'.

Red plastic caps are marked "ORPLS 1106 WAPLS 17372". All rebar accessories have "bearing object" signs wired to them.

Nailed "Witness" sign to the railroad tie post South of corner monument.

LOCATION AND COMMENTS: Corner is located at the intersection centerline of Koebcke Road and field berm extending South.

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-20

RECEIVED BY
Umatilla County Surveyor
Date: 10/11/2018
Rec'd By: JMA
No.: 18-087-R

\4N33N-3