

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 05/29/01

CORNER DESIGNATION: C-1, West 1/4 Corner Section 6, T4N., R35E., W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner was originally established by William Odell, U.S. Deputy Surveyor, under Contract No. 114 dated July 2nd, 1866. Original Notes state: Set 1/4 Sec. post cor.: drove charred stake, dug pits and raised mound as per instructions. Corner was re-established by Staebler, in 1988, under Survey No. 88-9-A. Record states: Set 1" x 30" G.I.P. with flared base and 2 1/2" brass cap 6" above the ground. No accessories were set.

MONUMENT AND ACCESSORIES FOUND: Found a 2 1/2" brass cap, 18" below ground, marked as shown in "Monument Marking Detail".

MONUMENT MARKING DETAIL:

T4N
1/4
R34E | R35E
S1 | S6
1988
RLS 1333

NEW ACCESSORIES TO EXISTING MONUMENT:

From which:

- A silver deep-1 magnet, 18" below the ground, bears N 63° E, 37.7 feet.
- A purple deep-1 magnet, 18" below the ground, bears S 52° E, 41.4 feet.
- A blue deep-1 magnet, 18" below the ground, bears S 28° W, 26.6 feet.
- An orange deep-1 magnet, 18" below the ground, bears N 55 1/2° W, 32.6 feet.
- Buried bearing object alongside each deep-1 magnet.

LOCATION AND COMMENTS:

Corner is located in farmed area.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 804280.00
E = 8712224.62

FIRM: William R. Wells, PLS

P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

Mark Hammersla

4N35C1

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-02

02-12-C