

OREGON CORNER RESTORATION FORM

Section 1 Township 4N Range 34 E

County Umatilla Date 5-11-89

C-25

CORNER DESIGNATION

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals/Surveys, etc. Originally a post, pits, and mounds (1865), CS.Kb. 88-9-A


Monument(s) & Accessories Found: (Condition and Source)

This corner falls on a very slight ridge, like there has been an old fence line east and west a very long time ago. Nothing N. - S. and the whole area is being cultivated.

Found 1" x 30" G.I.P. 6" above ground.

Monument Detail

Sketch



Monument Set (Procedures and Description)

Reset 1" x 30" G.I.P. w/flared base and 2 1/2" brass cap 18" below ground. Set steel fence post near the B.C. with yellow witness sign attached.

New Accessories

Set 5/8" x 30" iron rebar w/Alum. cap "KEL 933" 1' East of 4" iron pipe 12' high 453.37. Angle 183°38'18" to RR iron and 342.40 feet.

Location & Comments

Corner is located along plow line.

Compass Declination

Firm/Agency Dave Krumbein, P.L.S., P.E.

Umatilla County Surveyor

Address 3920 Westgate

Pendleton, OR 97801

Party Chief

Notes

Witness

Surveyor's Seal

RECEIVED BY
 Umatilla County Surveyor
 Date 5-11-89
 No. 89-55-R

