


History of original corner establishment:

This corner was originally established by William H. Odell, U.S. Deputy Surveyor, under Contract No. 114 dated July 2, 1866. The original notes state that at the corner a post was set for the corner with a driven charred stake and pits and mounds constructed as per instructions.

In 1904, under County Survey No. 200, County Surveyor Kimbrell recovered the corner position and noted it's position relative to the Northeast corner of Section 13.

The 1939 survey for County Road No. 880 also indicates a general location of the corner relative to the alignment of County Road No. 880.



J-15

Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

Found 6" steel pipe, 6 feet high, at the intersection of field lines running East, South and North. The position of the steel pipe was verified by measurements to fence corners and field corners to the North, South, East and West and was accepted as the best remaining evidence of the position of the original corner.

Description of monument and accessories established to perpetuate the original location of this corner:

At a point just West of the 6" steel fence post, set a 2 1/2" brass cap on 1 1/4" galvanized iron pipe, 28" in the ground and surrounded with a mound of earth and stone. Referenced the corner monument as follows:

A 5/8 inch by 30" iron pin bears S 86° E 41.7'. Placed bearing object sign on the locust post just East of the pin.

A brass washer stamped PLS 1106, nailed to the East side of PP&L power pole no. 153901, about 1' above ground, bears S 82° 38' W 524.9'. Placed bearing object sign on the power pole.

The 5/8 inch iron pin monumenting the Northeast corner of Parcel 1 of Partition Plat No. 1991-11 bears S 01° 01' 15" E 726.63'.

The 5/8 inch iron pin monumenting the Northwest corner of Parcel 1 of Partition Plat No. 1991-11 bears S 12° 43' 34" W 794.11'.

Set steel fence post 1' North of corner and attached witness corner sign.

Note: This corner falls at the corner of actively farmed fields and no closer locations for references are available.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date 10-91

Rec'd By K.R.

No. 91-28-R