

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 06/01/01

CORNER DESIGNATION: L-1, West 1/4 Corner of Section 18, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Wm. H. Odell under Contract 114, dated July 2nd 1866. Record states: Set 1/4 Sec. post cor.; drove charred stake, dug pits and raised mound as per instructions. Survey by John Kimbrell dated November 10, 1913, Umatilla County Survey Book 2, Page 241, calls corner as found.

MONUMENT AND ACCESSORIES FOUND: Found a 5/8" iron rebar with a yellow plastic cap stamped "OR 2166 LS". This corner was re-established by LS 2166 during his Survey for the Plat of Tillman Addition recorded in Book 13, Page 122, Record of Town Plats.

MONUMENT MARKING DETAIL:

T4N
R34E|R35E Note: Corner is monumented with a 5/8" rebar with
1/4 yellow plastic cap marked "OR 2166 LS".
S13|S18

NEW ACCESSORIES TO EXISTING MONUMENT:

A silver deep-1 magnet buried 18" in ground bears N 30 1/2° E, 43.2 feet.
A purple deep-1 magnet buried 18" in ground bears S 61° E, 52.5 feet.
A blue deep-1 magnet buried 18" in ground bears S 06° W, 48.8 feet.
An orange deep-1 magnet buried 18" in ground bears N 55° W, 29.1 feet.
Buried bearing object signs alongside the deep-1 magnets. Attached "witness" sign to Pacific Power and Light Pole #13940, and nailed a bearing object sign indicating approximate bearing and distance to corner monument.

LOCATION AND COMMENTS: Corner falls in a farmed field.

OREGON STATE PLANE CO-ORDINATES, Oregon North, NAD 83(91), International Feet:

N: 793693.87
E: 8712573.88

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Mark Hammersla
W4N35L1

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-02

02-12-C