

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 11/16/12

CORNER DESIGNATION: N-19, The North Quarter Corner of Section 23, Township 4 North, Range 34 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by William H. Odell under contract No. 114, dated July 2, 1866. Notes State: Set post corner for 1/4 Section, drove charred stake dug pits & raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Held the intersection of the centerline of Mansfield Road and a field berm extending West as the best remaining evidence of the corner.

MONUMENT MARKING DETAIL:

T4N R34E

1 S14

4 S23

2012

PLS 54657

MONUMENT SET: At the corner point set a 2 3/8" dia. brass cap on a 1 1/4"x30" galvanized iron pipe with the top of the cap buried 8" below the gravel road surface. Monument marked as shown in "Monument Marking Detail".

From which:

A 5/8" x 24" iron rebar with a 1 1/4" purple plastic cap marked "Wells Surveying 54657PLS", on a small bank between the East edge of Mansfield road and the edge of a farmed field bears North 25° East, 24.3 feet.

A 5/8" x 24" iron rebar with a 1 1/4" purple plastic cap marked "Wells Surveying 54657PLS", 5 feet Northwesterly of Pacific Power and Light Pole No. 235901 bears South 08° East, 123.9 feet.

A 5/8" x 24" iron rebar with a 1 1/4" purple plastic cap marked "Wells Surveying 54657PLS", on a small bank between the West edge of Mansfield road and the edge of a farmed field bears South 20° West, 41.4 feet.

A 5/8" x 24" iron rebar with a 1 1/4" purple plastic cap marked "Wells Surveying 54657PLS", 0.50' East of a railroad tie marker post bears South 89° West, 27.8 feet.

Wired bearing object signs to the three rebars and nailed bearing object sign and witness post sign to the railroad tie marker post.

LOCATION AND COMMENTS: Corner is located in the visual centerline of Mansfield road with a farmed field berm extending West.

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

/4N34N19

RECEIVED BY

Umatilla County Surveyor

Date: 11/16/2012

Rec'd By: J. Res

No.: 12-143-B

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Jason M. Wells
OREGON
NOVEMBER 29, 2010
JASON M. WELLS
54657PLS

RENEWS: 6-30-14