


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R-9

**History of original corner establishment:**

The original corner was established by Wm. H. Odell on July 2, 1866, under GLO contract No. 114, as follows:

Set post with a charred stake, dug pits and mounds.



**Description of corner evidence found:**

The original corner position is lost.

**Description of monument and accessories I established to perpetuate the original location of this corner:**

At the intersection of the fence on the South line of Section 21 and the centerline of Sand Hollow Road, I set a 1" x 18" iron pipe, A 2 1/2" brass cap attached is marked as shown in the above diagram.

A 5/8" x 30" rebar set 28" into the ground, with a red plastic cap stamped PLS 54871, bears S88°E, 30.2 feet.

A 5/8" x 30" rebar set 28" into the ground, with a red plastic cap stamped PLS 54871, bears S14°E, 103.1 feet.

A 5/8" x 30" rebar set 28" into the ground, with a red plastic cap stamped PLS 54871, bears S11°W, 118.7 feet.

A 5/8" x 30" rebar set 28" into the ground, with a red plastic cap stamped PLS 54871, bears N15°W, 86.8 feet.

I hereby certify the above corner point was perpetuated as hereon described on October 1, 2002. Bearings are true.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Thomas S. Frost*

OREGON  
JANUARY 19, 1999  
THOMAS S. FROST  
54871

Office of  
State of

County of

I hereby certify that the within instrument was filed in this office

for record on the, day of

(COUNTY OFFICIAL)

by

(DEPUTY)

*PLANS 12-31-03*