

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 06/12/01

CORNER DESIGNATION: A-15, North 1/4 Corner of Section 3 only, T4N., R35E., W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: None, Corner was not originally established.

MONUMENT AND ACCESSORIES FOUND: None.

**MONUMENT MARKING DETAIL:**

T5N R35E

-----  
1/4 S3

T4N R35E

2001

PLS 1106

**MONUMENT SET:**

At point determined by survey as shown on the accompanying Record of Survey, set a 5/8" x 30" iron rebar with a 2" aluminum cap, marked as shown in "Monument Marking Detail".

From which:

A brass washer, stamped "PLS 1106", 1.0 feet above ground level, in Pacific Power and Light pole #343001, bears N 55° E, 53.6 feet.

A purple deep-1 magnet, 18" below ground level, bears S 30 1/2° E, 61.6 feet.

A blue deep-1 magnet, 18" below ground level, bears S 55 1/2° W, 58.6 feet.

The center of a York and Watts Road sign post bears N 09 1/2° W, 32.8 feet.

Buried bearing object signs with deep-1 magnets and attached bearing object sign to power pole.

**LOCATION AND COMMENTS:**

Corner is located in the "triangle" area of York Road running South and East, and Watts Road running West.

OREGON STATE PLANE CO-ORDINATES, Oregon North, NAD83(91), International Feet:

N: 806454.71

E: 8730603.86

FIRM: William R. Wells, PLS

P.O. Box 1696

Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT

Mark Hammersla

4N35A15

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Will. R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*Renews 6-30-02*

*02-12-C*