

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 06/08/01

CORNER DESIGNATION: C-17, West 1/4 Corner of Section 2, T4N., R35E., W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Wm. H. Odell under Contract No. 114, dated July 2nd, 1866. Record states: Set post Cor. for 1/4 Sec., on level; drove charred stake, dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T4N R35E
1/4
S3 | S2
2001
PLS 1106

MONUMENT SET:

At a point determined by single proportionate measurement as shown on the accompanying Record of Survey, set a 2 1/2" brass cap on a 1" x 30" galvanized iron pipe, with cap buried 16" below ground, marked as shown in "Monument Marking Detail".

From which:

- A silver deep-1 magnet, buried 16" in the ground, bears N 55° E, 35.4 feet.
- A purple deep-1 magnet, buried 16" in the ground, bears S 32 1/2° E, 34.2 feet.
- A blue deep-1 magnet, buried 16" in the ground, bears S 55 1/2° W, 45.2 feet.
- A brass washer stamped "PLS 1106", 2.0 feet above ground level, in Pacific Power and Light pole #039500, bears N 62 1/2° W, 298.2 feet.
- Buried bearing object signs alongside the deep-1 magnets.
- Attached bearing object tag to PP & L power pole.

LOCATION AND COMMENTS: Corner falls in a farmed field.

OREGON STATE PLANE CO-ORDINATES, North Zone, NAD 83(91), International Feet:

N: 804768.30
E: 8733258.04

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT
Mark Hammersla
V4N35C17

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-02

02-12-C