

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 10/12/00

CORNER DESIGNATION: E-15

PREVIOUS RENEWALS/SURVEYS ETC.: This corner was originally established by William Odell, US. Deputy Surveyor, under Contract No. 114, dated 2 July, 1866. The original notes state: Set post cor, for 1/4 Sec., drove charred stake, dug pits and raised mound as per instructions.

Remonumented by Wells in 1993, Umatilla County Survey Record #93-42-B. Notes state: Found 3" nail, embedded in the ground, below oil mat surface of the County Road. Old field berms extend East and West from the nail. The origin of the nail is unknown, but it is accepted as the best remaining evidence of the original corner. At the position of the found nail, set a 2 1/2" brass cap on 1 1/4" by 30" galvanized iron pipe, 36" in the ground. (The top of the brass cap is buried 6" below the paved road surface). Referenced the corner monument as follows: A railroad spike, driven flush with the paved road surface, bears North, 85.2'. A 5/8" by 30" iron pin with 1 1/2" yellow plastic cap bears N 89 1/2°E, 22.45'. A railroad spike, driven flush with the paved road surface, bears South 54.45'. A 5/8" by 30" iron pin with 1 1/2" yellow plastic cap bears N 70° W, 24.75'. Set steel fence post near the Easterly reference pin and attached witness corner sign and bearing object sign. Wired bearing object sign to the iron pin reference located N 70° W of the corner monument. The 1 1/2" yellow plastic caps are marked "W.R. Wells, PLS 1106".

MONUMENT AND ACCESSORIES FOUND: 2 1/2" brass cap marked as shown in "monument marking detail". A railroad spike, driven flush with the paved road surface, bears North, 85.2 feet. A 5/8" by 30" iron pin with 1 1/2" yellow plastic cap bears N 89 1/2° E, 22.45 feet. A railroad spike, driven flush with the paved road surface, bears South, 54.45 feet. A 5/8" by 30" iron pin with 1 1/2" yellow plastic cap bears N 70° W, 24.75'. Found steel fence post near the Easterly reference pin with witness sign and bearing object sign. Found bearing object sign on reference pin located N 70° W of the corner monument.

MONUMENT MARKING DETAIL:

T4N R35E
1/4 S3
S10
1993
PLS 1106

LOCATION AND COMMENTS: Found monument and accessories as described in 1993 record.

OREGON STATE PLANE COORDINATES, North Zone, NAD 83(91), International Feet:

N = 802168.54
E = 8730707.93

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells
Kevin Snively
W4N35E15

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-02

02-12-C