

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 05/25/01

CORNER DESIGNATION: E-9, Northwest Corner of Section 9, T4N., R35E., W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Wm. H. Odell under Contract No. 114, dated July 2nd, 1866. Record states: Set post Cor. for Secs. 4, 5, 8 & 9; drove charred stake, dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T4N R35E
S5 | S4
S8 | S9
2001
PLS 1106

MONUMENT SET:

Accepted fence corner with fences extending South and West as best remaining evidence of the original corner location and set a 2 1/2" x 30" aluminum pipe with 2 1/2" aluminum cap, 29" in the ground. New monument is set 6" NE of fence corner post, stamped as shown in "Monument Marking Detail".

From which:

A silver deep-1 magnet, buried 18" below ground level, bears N 52° E, 24.8 feet.

A brass washer stamped "PLS 1106", 1 foot above ground line in a locust fence post bears S 01° W, 36.6 feet.

The base of a steel fence post in fence extending West, bears N 89° W, 49.0 feet.

An orange deep-1 magnet, buried 18" below ground level, bears N 23° W, 33.3 feet.

Attached bearing object signs alongside deep-1 magnets. Attached bearing object signs to both post accessories. Attached "witness" sign in wood fence corner post by corner monument.

LOCATION AND COMMENTS: Corner is located at a fence corner with fences extending South and West.

OREGON STATE PLANE CO-ORDINATES, North Zone, NAD 83(91), International Feet:

N: 802079.99

E: 8722743.42

FIRM: William R. Wells, PLS

P.O. Box 1696

Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT

Mark Hammersla

W4N35E9

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-02

02-12-C