

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 06/01/01

CORNER DESIGNATION: G-1, West 1/4 Corner of Section 7, T4N., R35E., W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Wm. H. Odell, under Contract No. 114, dated July 2nd, 1866. Record states: Set 1/4 cor.; drove charred stake, dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T4N
R34E R35E
1/4
S12|S7
2001
PLS 1106

MONUMENT SET: At position determined by single proportion measurement between the recovered Southwest Corner of Section 6 and the recovered West 1/4 Corner of Section 18, set a 2 1/2" aluminum cap on 2 1/2" x 30" aluminum pipe, stamped as shown in "Monument Marking Detail".

From which:

- A silver deep-1 magnet, buried 18" in ground, bears N 34° E, 30.0 feet.
 - A purple deep-1 magnet, buried 18" in ground, bears S 24 1/2° E, 39.2 feet.
 - A blue deep-1 magnet, buried 18" in ground, bears S 40° W, 42.6 feet.
 - An orange deep-1 magnet, buried 18" in ground, bears N 28° W, 30.6 feet.
- Buried bearing object signs alongside the deep-1 magnets.

LOCATION AND COMMENTS: Monument is located 3.0 feet South of North edge of gravel road, 6" below road surface. There is a North-South field line about 50 feet West of corner.

OREGON STATE PLANE CO-ORDINATES, North Zone, NAD83(91), International Feet:

N: 798991.43
E: 8712387.12

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Mark Hammersla
V4N35G1

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-02

02-12-C