


T 4N, R 35E. , W.M.

Corner Code No. G-13

Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by William Odell, U.S. Deputy Surveyor, under Contract No. 114, dated 2 July, 1866. The original notes state: Set post Cor. for 1/4 Sec., drove charred stake, dug pits and raised mound as per instructions. This corner was recovered and used in the subdivision of Section 16, during J.C. Arnold's County Survey in October, 1889.



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

Found ancient fence corner with fence remains extending to the North and a field berm extending to the East. This location agrees within 2 1/2' of J.C. Arnold's remeasurement distance reported in his 1889 survey. The fence corner was accepted as the best remaining evidence of the original corner location.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2 1/2" brass cap on 1 1/4" by 30" galvanized iron pipe, 24" in the ground and surrounded with a mound of earth and stone.

Set steel fence post 2' North of the corner and attached witness corner sign.

There are farmed fields West and South of the corner point.

Referenced the corner as follows:

- A 5/8" by 30" iron pin with 1 1/2" yellow plastic cap bears N 10 1/2°W 12.7'.
A 5/8" by 30" iron pin with 1 1/2" yellow plastic cap bears N 29°E 27.8'.
A 5/8" by 30" iron pin with 1 1/2" yellow plastic cap bears N 37 1/2°E 7.5'.
A 5/8" by 30" iron pin with 1 1/2" yellow plastic cap bears N 78 1/2°E 18.1'.

The 1 1/2" yellow plastic caps are marked "W.R. Wells, PLS 1106".

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Expires 12-31-94

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date 5-93
Rec'd By KR
No. 93-42-B