

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 12/27/01

CORNER DESIGNATION: G-5, West 1/4 Corner of Section 8, T4N., R35E., W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Wm. H. Odell, under Contract No. 114, dated July 2nd, 1866. Record states: Set post Cor. for 1/4 Sec.; drove charred stake, dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND:
None.

MONUMENT MARKING DETAIL:

T4N R35E
1/4
S7/S8
2001
PLS 1106

MONUMENT SET:

Held centerline of East-West Road, on line between recovered Southeast Corner of Section 7 and re-established Northeast Corner of Section 7 as best remaining evidence of original corner location. At position determined by survey, set a 2 1/2" brass cap on 1" x 30" galvanized iron pipe, 38" in the ground. Brass cap is set 8" below centerline of existing gravel road and is marked as shown in "Monument Marking Detail".

From which:

A 5/8" x 30" iron rebar with a yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears S 77° E, 51.6 feet, cap set flush with ground.

A 5/8" x 30" iron rebar with a yellow plastic cap stamped "OR PLS 1106, WA PLS 17372" bears S 56° W, 22.9 feet, cap set flush with ground.

A brass washer stamped "PLS 1106", nailed 1 foot above ground to power guy pole number 079502, bears N 69° W, 67.3 feet.

A brass washer stamped "PLS 1106", nailed 1 foot above ground to power pole number 079501, bears N 16° W, 25.0 feet.

Nailed bearing object signs to power and guy pole and wired bearing object signs to iron rebar accessories. Nailed "witness" sign to power pole.

LOCATION AND COMMENTS:

County Road records were consulted. There are no calls for the corner in the original County Road notes.

OREGON STATE PLANE CO-ORDINATES, North Zone, NAD 83 (91), International Feet:

N: 799272.12

E: 8717537.18

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Mark Hammersla

V4N35G5



Will. R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-02

02-12-C