

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 10/05/00

CORNER DESIGNATION: L-5, West 1/4 Corner of Section 17, T4N., R35E., W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: This corner was originally established by William Odell, U.S. Deputy Surveyor, under Contract No. 114 dated July 2nd, 1866. The original notes state: Set post Cor. For 1/4 Sec., drove charred stake, dug pits and raised mound. Corner remonumented by K.E.L. in 1982 under Survey No. 83-76-C. Survey states: Found 5/8" iron rod, set B.C. in its place, found no record of 5/8" rod in surveyors office.

MONUMENT AND ACCESSORIES FOUND: At a point in center of paved road (LaMarr Gulch), with field line running east-west, found a 2 1/2" brass cap buried 8" below road surface, marked as shown in "Monument Marking Detail".

MONUMENT MARKING DETAIL:

T4N R35E
1/4
S18|S17
1982
LS 933

NEW ACCESSORIES TO EXISTING MONUMENT:

A brass washer stamped "PLS 1106", 1.0 above ground on a Pacific Power and Light pole, bears N 23° E, 62.7 feet.

A brass washer stamped "PLS 1106", 1.0 above ground on a Pacific Power and Light pole #170561, bears S 87° E, 19.9 feet

A 5/8" x 30" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", 2" above ground, bears "S 25° W, 52.8 feet.

A brass washer stamped "PLS 1106", 1.0 above ground on a Pacific Power and Light guy pole, bears N 86° W, 66.8 feet. Set steel fence post near with bearing object and "witness" signs.

All accessories have bearing object signs attached. Power poles East and West of Corner have "witness" signs attached.

LOCATION AND COMMENTS: Corner falls in LaMarr Gulch Road.

OREGON STATE PLANE COORDINATE, Oregon North, NAD 83(91), International Feet:

N = 793776.50

E = 8717699.06

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801


COMPASS DECLINATION: 20° East

Surveyor's Seal

Witnesses: Jason Wells
Kevin Snively
VN35L5



William R. Wells



Expires 6-30-02

02-12-C