

COUNTY: Umatilla DATE: 03/04/97

CORNER DESIGNATION: N-15, The North Quarter Corner of Section 22, T4N., R35E., W.M.

N-15

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by William H. Odell, GLO Contract No. 114, dated July 2, 1866. Survey notes state: Set post Cor. 1/4 Sec.; drove charred stake, dug pits and raised mound as per instructions. Corner re-monumented by PLS 933, Umatilla County Survey No. 83-156-C. Notes state: K.E.L. found R/R spike at location that called for a 5/8" i.rod on Co. Survey Drwg No's Q-711-Ax & Q-715-C. K.E.L. replaced R/R spike set by Wallulis in 1966 with a B.C.

MONUMENT AND ACCESSORIES FOUND: Found 1 1/2" brass cap in monument box, 0.5 feet below the road surface, in intersection of Key Road and McLean Road.

MONUMENT MARKING DETAIL:

Umatilla County
T4N R35E
1 S15
4 S22
1982
PLS 933
Surveyor

MONUMENT SET: Existing monument.
New Accessories:

A brass washer stamped "PLS 1106" nailed to a Pacific Power and Light Pole #155009, 1.0 foot above ground surface, bears N 65° E, 47.0 feet.

A brass washer stamped "PLS 1106" nailed to a Pacific Power and Light Pole #225940, 1.0 foot above ground surface, bears S 13° E, 118.3 feet.

A brass washer stamped "PLS 1106" nailed to a Pacific Power and Light Pole #224915, 1.0 foot above ground surface, bears S 23° W, 61.1 feet.

A brass washer stamped "PLS 1106" nailed to a Pacific Power and Light Pole #155005, 1.0 foot above ground surface, bears N 14° W, 201.0 feet.

LOCATION & COMMENTS: Corner at intersection of McLean and Key Roads.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Kelly Snively
Troy Baker

OREGON NORTH STATE PLANE CO-ORDINATE FOR CORNER, NAD 83(91), INT. FEET:

N: 791650.30

E: 8731018.77

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-98

97-141-C