

OREGON CONFIRMATION FORM

COUNTY: Umatilla DATE: 03/05/97

CORNER DESIGNATION: R-13, The Northwest Corner of Section 27, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by William H. Odell, GLO Contract No. 114, dated July 2, 1866. Survey notes state: Set post Cor. for Secs. 21, 22, 27 & 28, on land slopes to the E.; drove charred stake, dug pits and raised mound as per instructions.

Corner re-monumented by PLS 933, Umatilla County Survey Record No. 83-156-C. Notes state: K.E.L. found stone mound and old fence corner, set B.C. in center of stone mound.

MONUMENT AND ACCESSORIES FOUND: Found 2 1/2" brass cap on galvanized iron pipe level with ground surface, steel fence post with witness sign attached 1.0 foot North, in a mound of dirt in intersection of three cultivated fields.

MONUMENT MARKING DETAIL:

Umatilla County  
T4N R35E  
S21 | S22  
S28 | S27  
1982  
PLS 933  
Surveyor

MONUMENT SET: Existing monument.

New Accessories:

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 48° E, 20.0 feet.

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 39° E, 19.8 feet.

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 43° W, 18.9 feet.

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 46° W, 17.4 feet.

All iron rods are 1.6 feet below the ground surface with bearing object signs attached.

LOCATION & COMMENTS: Corner is at the intersection of 3 wheatfields with field lines running North-South and East.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Kelly Snively  
Troy Baker

OREGON STATE PLANE NORTH CO-ORDINATE  
FOR CORNER, NAD 83(91), INT. FEET:

N: 786232.57  
E: 8728492.80

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*Renews 6-30-98*