

OREGON CORNER RE-CORRIGATION FORM

COUNTY: Umatilla DATE: 03/04/97

CORNER DESIGNATION: R-15, The North Quarter Corner of Section 27, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by William H. Odell, GLO Contract No. 114, dated July 2, 1866. Survey notes state: Set post Cor. for 1/4 Sec.; drove charred stake, dug pits and raised mound as per instructions. N.W. Cor. of Stone Chimney, brs. E., 15 lks.

Corner re-monumented by PLS 933, Umatilla County Survey Record No. 83-156-C. Notes state: K.E.L. found iron rod, Co. Survey Drwg No. C-12-C, replaced rod with B.C.

MONUMENT AND ACCESSORIES FOUND: Found 2 1/2" brass cap on galvanized iron pipe below backtop surface on North-South McLean Road centerline.

MONUMENT MARKING DETAIL:

Umatilla County  
T4N R35E

1 S22  
4 S27  
1982  
PLS 933  
Surveyor

MONUMENT SET: Existing monument.

New Accessories:

A brass washer stamped "PLS 1106" nailed to Pacific Power and Light Pole #225001, 1.0 foot above the ground surface, bears N 11° E, 208.2 feet.

A brass washer stamped "PLS 1106", nailed to Pacific Power and Light Pole #225004, 1.0 foot above the ground, bears S 81° E, 30.6 feet.

A brass washer stamped "PLS 1106", nailed to Pacific Power and Light Pole #224000, 1.0 foot above the ground, bears S 88° W, 21.5 feet.

A 5/8" x 30" iron rod with a yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears N 13° W, 81.6 feet.

Bearing object sign attached to iron rod.

Bearing object signs attached to PP&L Poles facing the brass cap.

LOCATION & COMMENTS: Corner is located in McLean Road centerline, Northwest of a barn.

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Kelly Snively  
Troy Baker

OREGON STATE PLANE NORTH CO-ORDINATE  
FOR CORNER, NAD 83(91), INT. FEET:

N: 786276.13  
E: 8731216.66

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*Renews 6-30-98*