

OREGON CORNER RE ORATION FORM

COUNTY: Umatilla DATE: 03/06/97

CORNER DESIGNATION: R-5, The Northwest Corner of Section 29, T4N, R35E, W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by William H. Odell, GLO Contract No. 114, dated July 2, 1866. Survey notes state: Set post Cor. for Secs. 19, 20, 29, & 30; drove charred stake, dug pits and raised mound as per instructions.

Corner re-monumented by PLS 933, Umatilla County Survey Record No. 83-156-C. Notes state: K.E.L. found 1/2" iron rod, Co. Survey Drwg. No's J-112-A, K-73-B & M-12-B, K.E.L. replaced rod with B.C.

MONUMENT AND ACCESSORIES FOUND: Found 2 1/2" brass cap on galvanized iron pipe 0.3 feet below ground surface, 0.7 feet West from 7.0 foot high 3 1/2" diameter pipe. Also found a 1" steel rod 2.5 feet West of brass cap and buried 1.5 feet.

MONUMENT MARKING DETAIL:

Umatilla County
T4N R35E
S19 | S20
S30 | S29
1982
PLS 933
Surveyor

MONUMENT SET: Existing monument.

New Accessories:

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 46° E, 11.7 feet.

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 50° E, 11.0 feet.

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 47° W, 15.6 feet.

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 49° W, 14.8 feet.

All iron rods are 1.5 feet below the surface of ground with bearing object signs attached.

Attached witness sign to nearby 7 foot by 3 1/2 inch pipe.

LOCATION & COMMENTS: Located in field edge running East and West.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Kelly Snively
Troy Baker

OREGON NORTH STATE PLANE CO-ORDINATE FOR CORNER, NAD 83(91), INT. FEET:

N: 785808.62
E: 8717714.95

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-98