

OREGON CORNER REORIENTATION FORM

COUNTY: Umatilla DATE: 06/06/97

CORNER DESIGNATION: T-17, The East Quarter Corner of Section 27, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by William H. Odell, GLO Contract No. 114, dated July 2, 1866. Survey notes state: Set post Cor. for 1/4 Sec.; drove charred stake, dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Corner was re-established on line between the Northeast and Southeast corners of Section 27 at the Westerly projection of a fence extending Easterly from the corner area.

MONUMENT MARKING DETAIL:

T4N R35E
1
4
S27 ; S26
1997
PLS 1106

MONUMENT SET:

A 2 1/2" brass cap on a 1" x 30" galvanized iron pipe, 6" below surface of the intersection of two gravel roads, marked as shown in monument marking detail.

New Accessories:

- A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 48° E, 18.5 feet.
 - A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 17° E, 27.4 feet.
 - A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 49° W, 25.5 feet.
 - A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 42° W, 23.8 feet.
- All iron rods have bearing object signs and steel fence posts nearby with witness signs attached.

LOCATION & COMMENTS: Corner is located near the intersection of gravel roads going North-South and East.

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Kelly Snively
Jason Wells

OREGON STATE PLANE NORTH CO-ORDINATE FOR CORNER, NAD 83(91), INT. FEET:

N: 783639.99
E: 8733901.99

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-98