

OREGON CORNER RE-TORATION FORM

COUNTY: Umatilla DATE: 05/16/97

CORNER DESIGNATION: V-3, The North Quarter Corner of Section 31, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by Wm. H. Odell, GLO Contract No. 114, dated July 2, 1866. Notes state: Set post Cor. for 1/4 Sec.; drove charred stake, dug pits and raised mound as per instructions. Corner re-established by Z.F. Moody, GLO Contract No. 164, dated October 4, 1871. Notes state: Set post and made mound of earth for 1/4 Sec. Cor. Corner re-established by Jas. P. Currin and Jas. E. Noland, under Special Contract dated May 4, 1887. Notes state: Deposited charred stake, 12 ins. in the ground for 1/4 Sec. Cor., dug pits, 18 x 18 x 12 ins. E. & W. of stake, 5 1/2 ft. dist., raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it and in E. pit, drove stake, 2 ft. long, 2 ins. sq., 12 ins. in the ground marked 1/4 S. on N. face.

A stone was found for the corner by Willard Bradley, County Surveyor, in April 1915, during Bradley's County Survey No. 406.

MONUMENT AND ACCESSORIES FOUND: None. This corner position was re-established by calculation, with reference to County Survey No. 406, by Willard Bradley, dated April 1915, after recovering the South 1/16 corner and Southeast corners of Section 31 as indicated on Bradley's Survey Plat.

MONUMENT MARKING DETAIL:

T4N R35E
1 S30
4 S31
1997
PLS 1106

MONUMENT SET:

Set a 2 1/2" brass cap on a 1" galvanized iron pipe 20" below surface of cultivated field, cap marked as shown in Monument Marking Detail.

Accessories:

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 46° E, 18.6 feet.

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 26° E, 21.9 feet.

A 6" x 36" steel pipe bears S 69° W, 9.3 feet with a bearing object and witness sign attached.

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 32° W, 17.3 feet.

All iron rods are 20" below ground surface with bearing object tags attached.

LOCATION & COMMENTS: Located in cultivated field.

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Kelly Snively
Jason Wells

OREGON STATE PLANE NORTH CO-ORDINATE
FOR CORNER, NAD 83(91), INT. FEET:

N: 780462.02

E: 8715237.50

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1997
WILLIAM R. WELLS
1106

Renews 6-30-98