

COUNTY: Umatilla DATE: 05/14/97

CORNER DESIGNATION: V-5, The Northwest Corner of Section 32, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by Wm. H. Odell, GLO Contract No. 114, dated July 2, 1866. Notes state: Set post Cor. for Secs. 29, 30, 31 & 32; drove charred stake, dug pits and raised mound as per instructions. Corner re-established by Z.F. Moody, GLO Contract No. 164, dated October 4, 1871. Notes state: Set post and made mound of earth for Cor. to Secs. 31, 32, 29 & 30. Corner re-established by Jas. P. Currin and Jas. E. Noland, under Special Contract dated May 4, 1887. Notes state: Set pot 4 ft. long, 4 ins. sq., 24 ins. in the ground for Cor. to Secs. 29, 30, 31, & 32 marked:

T 4 N S 29 on N.E.

R 34 E S 32 on S.E.

S 31 on S.W. and S 30 on N.E. faces,

with 1 notch on S. & 5 notches on E. edges,

dug pits, 18 x 18 x 12 ins. in each Sec., 5 1/2 ft. dist. and raised mound of earth, 2 ft. high, 4 1/2 ft. base around it.

A stone was found for the corner by Willard Bradley, County Surveyor, April 1915, during Bradley's County Survey No. 406.

MONUMENT AND ACCESSORIES FOUND: None. This corner position was re-established by calculation, with reference to County Survey No. 406, by Willard Bradley, dated April 1915, after recovering the South 1/16 corner and Southeast corners of Section 31 as indicated on Bradley's Survey Plat.

MONUMENT MARKING DETAIL:

T4N R35E

S30 | S29

S31 | S32

1997

PLS 1106

MONUMENT SET:

Set a 2 1/2" brass cap on a 1" galvanized iron pipe 24" below ground surface, cap marked as shown in Monument Marking Detail.

Accessories:

A 5/8" x 30" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 67° E, 79.9 feet, steel fence post nearby with witness sign attached.

A 5/8" x 30" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 34° E, 79.1 feet, steel fence post nearby with witness sign attached.

A 5/8" x 30" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 66° W, 29.7 feet.

A 5/8" x 30" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 34° W, 46.4 feet.

All iron rods are 20" below ground surface with bearing object tags attached.

LOCATION & COMMENTS: Corner is located Northwest of an unimproved dirt road, in a cultivated field. Dirt road curves Northeast and South.

COMPASS DECLINATION: 18° East

Witnesses: Kelly Snively
Jason Wells

OREGON STATE PLANE NORTH CO-ORDINATE
FOR CORNER, NAD 83(91), INT. FEET:

N: 780501.01
E: 8717876.84

V-5

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Will. R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106
Renews 6-30-98