

OREGON CORNER REFORMATION FORM

COUNTY: Umatilla DATE: 06/19/97

CORNER DESIGNATION: V-7, The North Quarter Corner of Section 32, T4N., R35E., W.M.
 PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by Wm. H. Odell, GLO Contract No. 114, dated July 2, 1866. Notes state: Set post Cor. for 1/4 Sec.; drove charred stake, dug pits and raised mound as per instructions. Corner re-established by Z.F. Moody, GLO Contract No. 164, dated October 4, 1871. Notes state: Set post and made mound of earth for 1/4 Sec. Cor. Corner re-established by Jas. P. Currin and Jas. E. Noland, under Special Contract dated May 4, 1887. Notes state: Set post, 3 ft. long, 3 ins. sq., 24 ins. in the ground for 1/4 Sec. Cor., marked 1/4 S. on N. face, dug pits, 18 x 18 x 12 ins. E. & W. of post, 5 1/2 ft. dist. and raised mound of earth, 1 1/2 ft. high, 3 1/2 ft. base around it.

MONUMENT AND ACCESSORIES FOUND: None. Corner position was re-established by single proportion measurement between the Northwest and Northeast corners of Section 32 using the Currin and Noland distance record.

MONUMENT MARKING DETAIL:

T4N R35E
1 S29
 4 S32
 1997
 PLS 1106

MONUMENT SET:

Set a 2 1/2" brass cap on a 1" x 30" galvanized iron pipe 18" below surface of cultivated field, cap marked as shown in Monument Marking Detail.

Accessories:

- A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 44° E, 11.2 feet.
 - A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 43° E, 10.4 feet.
 - A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 40° W, 8.7 feet with a bearing object and witness sign attached.
 - A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 43° W, 11.2 feet.
- All iron rods are 18" below ground surface of cultivated field with bearing object tags attached.
 Set steel fence post N 12° W, 367 feet from monument with witness sign attached.

LOCATION & COMMENTS: Located in cultivated field approximately 200 yards East of Wildhorse Road, 400 yards South of Koepke farm house.

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Kelly Snively
 Jason Wells

OREGON STATE PLANE NORTH CO-ORDINATE
 FOR CORNER, NAD 83(91), INT. FEET:
 N: 780601.38
 E: 8720550.23

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

William R. Wells

OREGON
 JULY 22, 1977
 WILLIAM R. WELLS
 1106

97-141-C Renew 6-30-98