

OREGON COF R RE ORATION FORM

COUNTY: Umatilla DATE: 05/14/97

CORNER DESIGNATION: X-1, The West Quarter Corner of Section 31, T4N., R35E., W.M.
PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by Wm. H. Odell, GLO Contract No. 114, dated July 2, 1866. Notes state: Set 1/4 Sec. post cor.; drove charred stake, dug pits and raised mound as per instructions. Corner re-established by Z.F. Moody, GLO Contract No. 164, dated October 4, 1871. Notes state: Set post for 1/4 Sec. and made mound of earth. A stone was established for the corner by Willard Bradley, County Surveyor, in April 1915, during Bradley's County Survey No. 406.

MONUMENT AND ACCESSORIES FOUND: None. This corner position was re-established by calculation, with reference to County Survey No. 406, by Willard Bradley, dated April 1915, after recovering the South 1/16 corner and Southeast corners of Section 31 as indicated on Bradley's Survey Plat.

MONUMENT MARKING DETAIL:

T4N
R34E R35E
S36 | S31
1997
PLS 1106

MONUMENT SET:

Set a 2 1/2" brass cap on a 1" galvanized iron pipe 6" below ground surface, cap marked as shown in Monument Marking Detail.

Accessories:

A 5/8" x 30" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears N 42° E, 33.3 feet.

A 5/8" x 30" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears S 72° E, 28.6 feet.

A railroad spike stamped "PLS 1106" set in pavement, bears S 24° W, 21.9 feet.

A railroad spike stamped "PLS 1106" set in pavement, bears N 22° W, 24.0 feet.

Iron rods have bearing object tags attached.

A steel fence post with witness sign attached is 5.3 feet North of brass cap.

LOCATION & COMMENTS: Corner is approximately 8.0 feet East of of Pambrum Road.

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Kelly Snively
Jason Wells

OREGON STATE PLANE NORTH CO-ORDINATE FOR CORNER, NAD 83(91), INT. FEET:

N: 777770.47
E: 8712925.30

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-98

97-141-C