

OREGON CORNER REORIENTATION FORM

COUNTY: Umatilla DATE: 06/19/97

CORNER DESIGNATION: X-9, The East Quarter Corner of Section 32, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by Wm. H. Odell, GLO Contract No. 114, dated July 2, 1866. Notes state: Set 1/4 Sec. Cor. post; drove charred stake, dug pits and raised mound as per instructions. Corner was re-established in 1901 by John Kimbrell, County Surveyor as described in Record of Private Surveys Book 1, Page 474. Kimbrell set a 10 x 8 x 6" stone for corner.

MONUMENT AND ACCESSORIES FOUND: None. Corner position was re-established by single proportionate measure between the Southwest corner and the Northwest corner of Section 33 using the Kimbrell distance record from survey reported in Record of Private Surveys Book 1, Page 474.

MONUMENT MARKING DETAIL:

T4N R35E
 $\frac{1}{4}$
 4
 S32 | S33
 1997
 PLS 1106

MONUMENT SET:

Set a 2 1/2" brass cap on a 1" x 30" galvanized iron pipe 18" underground, monument marked as shown in monument marking detail. A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears N 39° E, 12.6 feet. A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears S 51° E, 18.0 feet. A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears S 33° W, 18.0 feet. A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 70° W, 16.0 feet. All iron rods have bearing object signs attached and are 18" below the surface of cultivated field. A witness sign is attached to railroad tie fence post bears West, 410 feet.

LOCATION & COMMENTS: Monument located in cultivated field 500 feet East of house at end of Ringel Road.

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Kelly Snively
 Jason Wells

OREGON STATE PLANE NORTH CO-ORDINATE FOR CORNER, NAD 83(91), INT. FEET:
 N: 778062.97
 E: 8723310.84

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

William R. Wells

OREGON
 JULY 22, 1977
 WILLIAM R. WELLS
 1106

Renews 6-30-98