

OREGON CORNER REORIENTATION FORM

COUNTY: Umatilla DATE: 06/17/97

CORNER DESIGNATION: Z-7, The South Quarter Corner of Section 32, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by W. H. Odell, GLO Contract No. 114, dated July 2, 1866.

Notes state:

Set post corner for 1/4 Sec., drove charred stake, dug pits and raised mound as per instructions.

Corner re-established by Z.F. Moody, GLO Contract No. 164, dated October 4, 1871. Notes state: Set post and made mound of earth for 1/4 Sec. cor.

Corner re-established by Jas. P. Currin & Jas. E. Noland, GLO Special Contract, dated May 4, 1887. Notes state: Set a post 36 x 3 x 3 ins. 12 ins. in the ground for 1/4 Sec. cor. marked 1/4 S. on N. face. Dug pits 18 x 18 x 12 E. & W. of cor. 5 1/2 ft. dist. I raised a mound of earth 1 1/2 ft. high 3 1/2 ft. base around post. Corner was re-established by John Kimbrell, County Surveyor, in survey reported in Record of Private Surveys Book 2, Page 138, dated 1909. Kimbrell set "a stone" for the corner.

MONUMENT AND ACCESSORIES FOUND: None. This corner position was re-established by single proportionate measurement between the Southwest corner of Section 32 and the Southeast corner of Section 33.

MONUMENT MARKING DETAIL:

T4N R35E	See discussion of this corner on Record
<u>1</u> S32	of Survey Map filed separately.
4	
T3N R35E	
1997	
PLS 1106	

MONUMENT SET:

Set a 2 1/2" brass cap on 1" x 30" galvanized pipe 20" below the surface of an unimproved road, cap marked as shown in Monument Marking Detail.

Accessories:

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 85° E, 18.4 feet.

A 3" x 5' pipe bears S 02° E, 32.6 feet.

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 52° W, 31.4 feet.

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 80° W, 16.2 feet.

Bearing object tags attached to iron rods and pipe. Iron rod in Southwest Quadrant has a steel fence post nearby with witness sign attached.

Set steel fence post 18' South of monument with witness sign attached.

LOCATION & COMMENTS: Corner is located on Rainwater Road about 5/8 mile West of Wildhorse Road intersection. Approximately 30' North of a grave head stone.

97-141-C

COMPASS DECLINATION: 18° East

Page 2 of 2
Surveyor's Seal **Z-7**

Witnesses: Kelly Snively
Jason Wells

OREGON STATE PLANE NORTH CO-ORDINATE
FOR CORNER, NAD 83(91), INT. FEET:

N: 775331.15
E: 8720746.02

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-98