

ERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 36E., W.M.

Corner Code No. R-23


Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by William Odell, U.S. Deputy Surveyor, under Contract No. 114, dated July 2, 1866. The original notes state:

Set basalt stone 5 X 10 X 15 ins. for 1/4 Sec. Cor. on hillside facing the West.

Map No. 84-30-B indicates a brass cap monument set at a fence intersection. I find no definable fence intersection and no evidence of the brass cap monument as of July, 1992.



Corner No. Compass Declination: 18.0°

Description of corner evidence found:

No evidence of the original corner stone was found after a diligent search of radius of 150' around the calculated corner point. The corner area is on a steep hillside covered with rock. Fences have been constructed through the corner area and many stones used as fence jacks.

The corner point was re-established by single proportion measurement between the Northeast and Northwest corners of Section 25. The re-established corner position lines up with fences approaching from the North and South.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2 1/2" brass cap on a 1 1/4" by 30" galv. iron pipe 22" in ground and surrounded with a mound of earth and stone. Cap marked as shown.

No trees are near corner, marked 4 rock outcrops for bearing objects:

A 4' x 4' x 2 1/2' out of ground rock outcrop bears S 32°E - 26.3'. Marked "XBO" on top West side.

A 4' x 2 1/2' x 1 1/2' rock in place bears S 01°W - 36.0'. Marked "XBO" on top Northwest corner.

A 8' x 5' x 3' out of ground rock outcrop bears S 06°W - 15.7'. Marked "XBO" on top Northwest corner.

A 6' x 6' x 3 1/2' out of ground rock outcrop bears N 0 1/2°E - 12.2'. Marked "XBO" on top South side.

Measured to "X" s on the "XBO" markings. Painted markings red.

Set steel fence post North of corner with witness corner sign attached.

REGISTERED PROFESSIONAL LAND SURVEYOR

William R Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by ..... (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

★ GPO-798-276

Date 7-92

Rec'd By JK

No. 92-79-B