

C LIFIED RECORD OF LAND CORNER MONUMENTATION


T 4N, R 36E., W.M.

Corner Code No. V-15
Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by William Odell, U.S. Deputy Surveyor, under Contract No. 114, dated July 2, 1866. The original notes state that at the corner a post was set for the corner from which:
A 40" pine bears S88°W 36 lks.
A 30" pine bears S88°W 138 lks.

In 1888, surveyor Arnold, during his County Survey No. 34, reestablished the corner as follows:
I reestablish the 1/4 sec. cor. on the line bet. secs. 27 and 34, from the stumps of the original bearing trees, which are in a great stage of decay, the letters "R" on each stump, can be readily seen. At true cor. pt. I set a basalt stone 14 by 8 by 8 ins. and 1/4 on N. face, 10 ins. deep, from which a pine tree, 6 ins. dia. bears N 2-30° E 56 links dist. A pine tree 5 ins. dia. bears N 75° W 50 links dist. no tree in limits S. of cor.



Corner No.
Compass Declination: 19.0°

Description of corner evidence found:

None, other than a north-south field line approaching the corner from the north. The corner area has been farmed for many years.

Description of monument and accessories I established to perpetuate the original location of this corner:

Reestablished the corner using the north-south field line to the north for departure and a straight line between the found North one-quarter corner of Section 33 and the found Northeast corner of Section 34 for latitude. At the reestablished corner point, I set a 2 1/2" brass cap on a 1 1/2" by 30" galv. iron pipe, 24" in the ground and surrounded with earth. From the new monument:

A 44" douglas fir bears S31°W 395.0' scribed 1/4 S 34 BT.
There are no other trees available for a witness, and any reference monuments set would be in the way of farming.

Set a steel fence post 1' east of the corner monument and attached witness corner sign.
The bearing tree has a bearing object sign on it.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

7-27-88

Office of Survey County of Umatilla
State of OR I hereby certify that the within instrument was filed in this office
for record on the 28th day of July, 1988
David H. Lamborn by Kathleen Lamborn
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date 7-88
Rec'd By [Signature]
No. 88-42-C

GPO-788-278