

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 36E., W.M.

Corner Code No. V-3

Note: Monument marked as shown below


History of original corner establishment:

This corner was originally established by William Odell, U.S. Deputy Surveyor, under Contract No. 114, dated July 2, 1866. The original notes state that at the corner a wood post was set from which:

A 6" pine bears N50°E 26 lks.
A 8" pine bears S70°W 18 lks.

In 1889, during his County Survey No. 46, Surveyor Arnold reestablished the corner after finding the original corner gone and the original bearing trees 42 feet apart, as follows:

"I find, from original notes, the point best to harmonize courses and distances and set a basalt stone 20 by 16 by 4 ins, on hill side facing N, stone marked 1/4 on N., from which one original B.T. bears S59°W 17' dist and the other B.T. bears N32°30'E 26' dist from stone".



Corner No.
Compass Declination: 19.0°

Description of corner evidence found:

Found 18" by 15" by 6" basalt stone as established by Arnold, firmly set, marked "1/4" on north face, from which:

A sawn 29" ponderosa pine stump bears S61°W 17.5' with scribes "BT" visible after opening the lower blaze.

Description of monument and accessories established to perpetuate the original location of this corner:

At the position of the found stone, set a 2 1/2" brass cap on a 1 1/2" by 30" galv. iron pipe, 24" in the ground and surrounded with a mound of earth. Buried marked stone in the earth mound. From the new corner monument:

A 10" ponderosa pine bears S88°W 18.4' scribed 1/4 S31 BT.
A 22" ponderosa pine bears N41°E 32.0' scribed 1/4 S30 BT.

Bearing trees have bearing object signs attached to them.

Set steel fence post east of corner and attached witness corner sign.

Corner is located 5' SW of a fence running N48°W from the corner area.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

7-27-88

Office of Survey County of Umatilla

State of OR. I hereby certify that the within instrument was filed in this office

for record on the 28th day of July, 1988

David P. Humbert by Richard L. Ambrose

(COUNTY OFFICIAL)

(DEPUTY) RECEIVED BY

Form R6-7100-57 (9/71)

Umatilla County Surveyor SPD-789-378

Date 2-88

Rec'd By [Signature]

No. 88-372-C