


CE... FIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 36E., W.M.

Corner Code No. X-1  
Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by Odell and Lewis, U.S. Deputy Surveyors, under Contract No. 110 dated February 7, 1885. The original notes state that at the corner a wood post, with charred stake and mound was set for the corner and the corner was referenced with pits dug in the earth.



Corner No.  
Compass Declination: 19.0°

Description of corner evidence found:

None.

Description of monument and accessories I established to perpetuate the original location of this corner:

This corner was reestablished by single proportion measure between the Northwest and Southwest corners of Section 31. At the reestablished corner position, set a 2 1/2" brass cap on a 1 1/2" by 30" galv. iron pipe 24" in the ground and surrounded with a mound of earth from which:

- A 17" ponderosa pine bears N31°E 69.3' scribed 1/4 S31 BT.
- A 22" ponderosa pine bears N12°W 95.1' scribed 1/4 S36 BT.

Attached bearing object signs to the bearing trees and set a steel fence post North of corner and attached witness corner sign.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

7-27-88

Office of Survey County of Umatilla  
State of OR I hereby certify that the within instrument was filed in this office  
for record on the 28<sup>th</sup> day of July 1988  
David H. Keambach by William R. Wells  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor OPD-788-578  
Date 7-88  
Rec'd By kt  
No. 88-42-C