

**CELESTIAL RECORD OF LAND CORNER MONUMENTATION**

T 4N, R 36E., W.M.


Corner Code No. X-5  
 Note: Monument marked as shown below

**History of original corner establishment:**

This corner was originally established by William Odell, U.S. Deputy Surveyor under Contract No. 114, dated July 2, 1866. The original notes state that at the corner a 5 by 9 by 15" marked stone was set for the corner.

In 1897, during his County Survey No. 95, John Kimbrell recovered the corner as stated below:

"We proceed to the place indicated by Mr. Kilgore, where we find lying on the ground a stone marked 1/4 and pointed out by said Kilgore as being at or very near the place where he had saw it years before. This point being so nearly in conformity with the lines and corner North and East as I had found them, I accept the point and set the stone in the ground and build a stone mound around it."



Corner No.  
 Compass Declination: 19.0°

**Description of corner evidence found:**

After a thorough search, found a 14 by 9 by 4" basalt stone lying loose on the hillside just downhill from computed corner position. The stone has a crude "4" chiseled on it. No trace of the stone mound built by John Kimbrell was found on this steep and rocky hillside.

**Description of monument and accessories I established to perpetuate the original location of this corner:**

At the computed corner position, which was computed by using John Kimbrell's record bearing from the Southeast Corner of Section 31 for departure, and Kimbrell's proportioned record latitude between the SE cor. Sec. 31, and the East 1/4 cor. of Section 30, for latitude, I set a 2 1/2" brass cap on a 1 1/2" by 30" galv. iron pipe, 24" in the ground and surrounded with a mound of earth and stone. Placed marked stone in the new mound. Referenced the new monument as follows:

- A 1 1/2" plastic cap, marked "W.R. Wells, PLS 1106", set on a 5/8" by 30" iron pin, bears N17°W 15.9". Wired bearing object sign to the iron pin.
- A 1 1/2" plastic cap, marked "W.R. Wells, PLS 1106", set on a 5/8" by 30" iron pin, bears S84°E 24.7". Wired bearing object sign to the iron pin.

Set steel fence post South of the corner and attached a witness corner sign.

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*William R. Wells*

OREGON  
 JULY 22, 1977  
 WILLIAM R. WELLS  
 1106

7-27-86

Office of Sumner County of Umatilla  
 State of OR I hereby certify that the within instrument was filed in this office  
 for record on the 28<sup>th</sup> day of July, 1988  
David H. Kimbrell by Deborah Ambrose  
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
 Umatilla County Surveyor  
 Date 7-88  
 Rec'd By JA  
 No. 88-42-C