

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 36E., W.M.

Corner Code No. X-9

Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by William Odell, U.S. Deputy Surveyor, under Contract No. 114, dated July 2, 1866. The original notes state that at the corner a wood post was set for the corner along with a charred stake and stone mound.

In 1897, during his County Survey No. 95, John Kiebrell recovered the corner as follows:

" I find the old 1/4 sec. corner which is old stone mound about 75 lks west of ravine as indicated and described by old settlers. From this corner I run S14°30'E between Secs. 32 and 33."

DIAGRAM

T4N R36E
1/4
S32 | S33
1988
PLS 1106

Corner No.
Compass Declination: 19.0°

Description of corner evidence found:

Found mound of stone about 75 lks west of a ravine. There are remains of an old post and rail fence running west from the stone mound.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the position of the stone mound, set a 2 1/2" brass cap on a 1 1/2" by 30" galv. iron pipe 24" in the ground and surrounded with a mound of earth and stone. Referenced the corner with reference monuments as follows:

A 1 1/2" plastic cap marked "W.R. Wells, PLS 1106", set on a 5/8" by 30" iron pin bears N68°W 15.0'. Set steel fence post by the reference monument and attached bearing object sign.

A 1 1/2" aluminum cap, marked as shown below, set on a 5/8" by 30" iron pin, bears N30°E 15.3'. Set steel fence post by reference monument and attached bearing object sign.

Set steel fence post east of corner and attached witness corner sign.

The aluminum cap on the reference monument is marked:



REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

7-27-88

Office of *Survey* County of *Umatilla*

State of *OR*, I hereby certify that the within instrument was filed in this office

for record on the *28th* day of *July*, 19 *88*

David H. Kiebrell by *William R. Wells*
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Survey *88-42-C*

Date *7-28*

Rec'd By *SA*

No. *88-42-C*