

CLASSIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 36E., W.M.

Corner Code No. Z-13


Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by Odell and Lewis, U.S. Deputy Surveyors, under Contract No. 110, dated February 7, 1885. The original notes state that at the corner a wood post was set from which:

- A 20" larch bears S74°W 20 lks.
- A 10" larch bears N40°E 18 lks.
- A 9" larch bears S3°E 22 lks.

This corner was also surveyed to and made an angle point in in the centerline of County Road No. 330, when this County Road was surveyed by John Kimbrell.



Corner No.
Compass Declination: 19.0°

Description of corner evidence found:

Angle point in County Road No. 330 with roads running East-West and Southwest.

Description of monument and accessories established to perpetuate the original location of this corner:

Reestablished corner position at the intersection of centerlines of County Road No. 330, now running East-West and Southwest from the corner point. This position was confirmed by survey measurements to corners to the East and West of the reestablished corner position. Since the reestablished corner position falls in the graded portion of the county road, the top of the monument was buried 8" below the ground surface. Set a 2 1/2" brass cap on a 1 1/2" by 30" galv. iron pipe, 38" in the ground from which:

- A 7" ponderosa pine bears S1°W 68.2' scribed T3N R36E S4 BT.
- A 10" douglas fir bears S69°E 87.3' scribed T3N R36E S3 BT.
- An aluminum nail in the North side of power pole No. 340001 bears N66°E 18.8'.
- The aluminum nail is about 6" above ground.

Attached bearing object signs to each bearing tree and set a steel fence post 11.5' North of corner and attached witness corner and bearing object signs.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

7-27-88

Office of Jury County of Umatilla
 State of Ore, I hereby certify that the within instrument was filed in this office
 for record on the 28th day of July, 1988
David H. Kimbrell by William R. Wells
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
 Umatilla County Surveyor
 Date 7-88
 Rec'd By [Signature]
 No. 88-12-C