

C. LIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 36E., W.M.


Corner Code No. Z-19

Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by Odell and Lewis, U. S. Deputy Surveyors, under Contract No. 110 dated February 7, 1865. The original notes state that a post was set for the corner from which

A 12" larch bears N60°W 30 lks.  
A 8" larch bears S40°E 38 lks.



Corner No.  
Compass Declination: 19.0°

Description of corner evidence found:

A 15" down and rotted western larch bears N60°W 19.8' with scribes "BT" on lower blaze and "S" on upper blaze, visible after opening blazes.

Description of monument and accessories established to perpetuate the original location of this corner:

At a point S60°E 19.8' from the root hole of the original bearing tree, set a 2 1/2" brass cap on a 1 1/2" by 30" galv. iron pipe 26" in the ground and surrounded with a mound of earth. From the new monument:

A 11" western larch bears N43°E 32.4' scribed 1/4 S35 BT.  
A 17" douglas fir bears S53°E 41.4' scribed 1/4 S2 BT.

Attached bearing object signs to the original bearing tree and the new bearing trees.

Set steel fence post east of corner and attached witness corner sign.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

7-27-88

Office of Sawyer County of Umatilla  
State of OR I hereby certify that the within instrument was filed in this office  
for record on the 28<sup>th</sup> day of July, 1988  
David H. Krambe by Kathleen K. Ambsrud  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

Umatilla County Surveyor

Date 7-88

Rec'd By KA

No. 88-42-C

GPO-788-278