


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

G-25

**History of original corner establishment:**

Corner established by George S. Pershin, U.S. Deputy Surveyor, under his Contract No. 304, dated September 19, 1878.  
 Surveyor General records state:  
 Set basalt stone 17x10x4 on South side of mountain for 1/4 Sec. Cor.  
 A pine 40 in. di. brs. S76°E, 295 lks dis. No other tree.



Corner remonumented by Robert F. Omeg, U.S. Deputy Surveyor, under his Contract No. 761, dated June 16, 1905.  
 Surveyor General records state:  
 Set a basalt stone 15x10x5 ins. 10 ins. in the ground for 1/4 sec. cor. marked 1/4 on W. face, from which:  
 A pine 40 ins. in diam. bears S76°E, 295 lks distant marked 1/4S7 BT.  
 And raised a mound of stone 2 ft. base and 1 ft. and a half high W. of cor.  
 No tree W. of the line within limits.

**Description of corner evidence found:**

Found a basalt stone 14x7x5", setting upright in mound of stone and marked 1/4 on W. face ("1/4" marks are not very distinct), from which:  
 A 42" ponderosa pine brs S76°E, 188.9' with scribes visible on partially healed blaze. (OBT)

**Description of monument and accessories | established to perpetuate the original location of this corner:**

At position of found corner stone...  
 Set 2½" aluminum cap on 2½" x 30" aluminum pipe 12" in ground to bedrock & surrounded with mound of earth & stone. Set 6' fence post South of corner with sign 54-4 attached. Cap marked as shown in corner diagram. Buried corner stone in mound.  
 New bearing trees established:  
 A 12" ponderosa pine brs S24½°W, 125.2' scribed 1/4S12 BT.  
 A 14" ponderosa pine brs S87½°W, 65.5' scribed 1/4S12 BT.  
 New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-4 to each BT and painted face of blaze & 6" red band around each BT.  
 Compass declination 19° East.

I hereby certify that the above described corner monument was properly remonumented by me on August 24, 1988.

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*William R. Wells*

OREGON  
 JULY 22, 1977  
 WILLIAM R. WELLS  
 1106

Office of... County Surveyor..... County of Umatilla  
 State of Oregon..... I hereby certify that the within instrument was filed in this office  
 for record on the 17<sup>th</sup> day of October..... 1988  
 Dated H. Humbert by Katherine Humbert  
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor  
 Date 10-88  
 Rec'd By KA  
 No. 88-64-B

\*GPO-591-971, 1988