

OREGON CORNER RESTORATION FORM

Section 10 Township 4N Range 37E

County Umatilla Date 6/21/94

CORNER DESIGNATION: J-11

Previous Renewals/Surveys, etc.

Corner originally established by U.S. Deputy Surveyor George S. Pershin under GLO contract No.332 dated July 29,1879. The Surveyor General records state: Set a Tamarack post on a N.W. face of a spur for 1/4 Sec.Cor. from which:

- A tamarack 5" ins. diam. brs. N 85° W, 58 lks.dist.
- A tamarack 14" ins. diam. brs. S 72° W, 92 lks.dist.

Monument(s) & Accessories Found: (Condition and Source)

Found remains of bottom of a blaze with axe marks in a rotted tamarack stump mound bear N 85° W, 38.3 feet (58 lks). A stump hole and remains of a rotted log bears S 72°W, 60.7 feet (92 lks) from re-established corner position.

Monument Detail: T4N R37E

S 9
 1/4 ----
 S 16
 1994
 PLS 1106

Monument Set (Procedures and Description):

At position established by reversed record bearing and distance from the recovered Section 16 bearing tree (S 85° E 38.3 ft.), set a 2 1/2" brass cap on a 1 1/2" x 30" galvanized iron pipe 25" in the ground with a surrounding earth and stone mound.

New Accessories:

- A 23" Douglas fir bears N 79°W, 11.1 ft. and is scribed 1/4 S9 BT.
 - A 20" Douglas fir bears N 14 1/2°W, 6.8 ft. and is scribed 1/4 S9 BT.
 - A 23" Douglas fir bears S 67°E, 35.2 ft. and is scribed 1/4 S16 BT.
 - A 20" western larch bears S 33°W, 41.8 ft. and is scribed 1/4 S16 BT.
- All bearing trees have blaze and a six inch red band painted around them. Nailed a brass washer stamped PLS 1106 and a bearing object and witness sign to each tree.
 Set a steel fence post 3 feet North of monument with witness corner sign attached.

Location & Comments: Corner is located on a North facing ridge approximately 100+/- from top of spur. Corner falls in dense underbrush.

Compass Declination: 18° E

Firm/agency: Tomkins-Wells Joint Venture
 Land Surveying
 P.O. Box 1696
 Pendleton, Oregon 97801

Party Chief: Greg Flowers
 Notes: Greg Flowers
 Witness: Todd Rosenbalm

RECEIVED BY

Umatilla County Surveyor
 Date 7-95
 Rec'd By KK
 No. 95-112-C

Surveyor's Seal

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

William R. Wells

OREGON
 JULY 22, 1977
 WILLIAM R. WELLS
 1106

renews 6/30/96