

**OREGON CORNER RESTORATION FORM**

**Section:** 11 & 14

**Township:** 4 North

**Range:** 37 East W.M.

**County:** Umatilla

**Date:** 02/25/2000

**Corner Designation:** J-17, closing corner common to Sections 11 & 14 only.

**Previous Renewals/Surveys, etc.:** This corner was originally set U.S. Deputy Surveyors Charles L. and William C. Campbell under their contract No. 733 dated March 22, 1901. The Surveyor General's notes state "set an ironstone 40x12x5 ins. 24 ins. in the ground, struck rock, raised mound of stone around for Closing Corner of Secs. 11 & 14, marked C.C. on the E. face, with 4 grooves on the S. & 2 grooves the E. faces. No trees in limits of line. Raised mound of stone 2 ft. base, 1 1/2 ft. high E. of Cor., pits impracticable".

**Monument(s) & Accessories Found (Condition & Source):** No evidence of the original corner was found.

**Monument Detail:** T4N R37E

CC  
S11  
S15 + -----  
S14  
2000  
LS 2820

**Monument Set (Procedures & Description):** S20°06'13"E 40.26' (61 lks. per Campbell) along the line between the found NE corner of Section 15 and the found East 1/4 corner of Section 15, set a 1"x 30" galvanized iron pipe 28" in the ground with a 2 1/2" brass cap attached and surrounded with a mound of earth and stone.

**New Accessories:** Set 6' steel fence post 2.4' West of the corner. A 5/8"x30" rebar (RM) with a yellow plastic cap stamped "TOMKINS SURVEYING" bears N6°E 26.8 feet. A 5/8"x30" rebar (RM) with a yellow plastic cap stamped "TOMKINS SURVEYING" bears N11°E 50.2 feet. A 36" Douglas fir with a closed blaze bears S75°W 57.1 feet. A 30" Douglas fir with a closed blaze bears N61°W 173.5 feet

All bearing trees have a 6" wide red band painted around them and bearing object signs attached.

All Reference monuments (RM) have a steel fence post with a bearing object sign attached set alongside.

**Location & Comments:** This corner is located on a steep, rocky, brush covered Southwest slope 100'± North of the South Fork of the Walla Walla River road near the gauging station above Harris Park.

**Compass Declination:**

19° East

**Firm/Agency:** Tomkins Land Surveying, Inc.  
20 E. Poplar, Suite 204  
Walla Walla WA 99362

**Party Chief:** Greg Flowers

**Notes:** Greg Flowers

**Witness:** Josh Martin

**Surveyor's Seal**

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Greg E. Flowers*  
OREGON  
JUNE 30, 1997  
GREG E. FLOWERS  
02820LS

RENEWS 12/31/01

*12/15/00*

RECEIVED BY  
Umatilla County Surveyor  
Date 12-00  
Rec'd By KE  
00-258-C