

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**


J-25

**History of original corner establishment:**

Corner established by George S. Pershin, U.S. Deputy Surveyor, under his Contract No. 304, dated September 19, 1878.

**Surveyor General records state:**

Set basalt stone 16x10x4, on West side of spur in mound of stone for Cor. to Sec 12, 13, 7 and 18. A fir 16 in. dia. brs. N33°E, 138 lks dist. No other trees.



Corner remonumented by Robert F. Omeg, U.S. Deputy Surveyor, under his Contract No. 761, dated June 16, 1905.

Surveyor General records state: Set a basalt stone 15x10x4 ins. 10 ins. in the ground for cor. of secs. 7, 12, 13 & 18, marked with 2 notches on the N and 4 notches on the S edges, from which: A fir 30 ins. diam. bears N45°E, 172 lks distant, marked T4NR38ES7 BT. and raised mound of stone 2 ft. base and 1 ft. and a half high W. of cor.

**Description of corner evidence found:**

Found a basalt stone 18x9x5", with no visible marks, lying flat, and an axe sharpened post lying in ground from which:

Root hole bears N45°E, 113.5'. The tree from this root hole, size indeterminent, is located about 100' downhill with axe marks.

A 1984 Boise Cascade location poster is on a 15" ponderosa pine which brs N30°E, 1.5 chains from corner stone.

**Description of monument and accessories established to perpetuate the original location of this corner:**

At position of found stone...

Set 2½" aluminum cap on 2½" x 30" aluminum pipe 24" in ground to bedrock & surrounded with mound of earth & stone. Set 6' fence post North of corner with sign 54-4 attached. Cap marked as shown in corner diagram. Buried corner stone in mound.

**New bearing trees established:**

- A 18" ponderosa pine brs N31½°E, 103.7' scribed T4NR38ES7 BT.
- A 18" douglas fir brs S25½°E, 73.3' scribed T4NR38ES18 BT.
- A 16" douglas fir brs S48°W, 57.1' scribed T4NR37ES13 BT.
- A 9" douglas fir brs N90°W, 58.7' scribed T4NR37ES12 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-4 to each BT and painted face of blaze & 6" red band around each BT.

Compass declination 19° East.

I hereby certify that the above described corner monument was properly remonumented by me on August 24, 1988.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of..... County Surveyor..... County of..... Umatilla.....  
State of..... Oregon....., I hereby certify that the within instrument was filed in this office  
for record on the 17<sup>th</sup> day of October, 1988  
..... David H. Kumbier by Kathleen J. Ambruce  
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY  
Umatilla County Surveyor  
Date 10-88  
Rec'd by KJ  
No. 88-64-B