

OREGON CORNER RESTORATION FORM

Section: 15
Township: 4N
Range: 37 EWM
County: Umatilla
Date: 03/01/00
Corner Designation: K-15, C-N 1/16 S.15

Previous Renewals/Surveys, etc.: N/A

Monument(s) & Accessories Found (Condition & Source): None found.

Monument Detail: TOMKINS SURVEYING

C-N 1/16
S. 15
T4N R37E
2000
PLS 2820

Monument Set (Procedures & Description): At surveyed position, set a 1 1/2" x 30" galvanized iron pipe with a 2 1/2" brass cap, marked as noted. Erected a stone mound 2' in diameter 1' high around the monument.

New Accessories: A steel fence post with a land survey monument sign was placed 1' North of the corner. 5/8" x 30" rebar with yellow cap stamped "Tomkins Surveying" were set in the ground as reference monuments, (R.M.). A steel fence post with a Umatilla County Bearing Object sign attached, set alongside each R.M. The R.M.s bear from corner as follows:

- N02°W, 20.0 feet.
- S72°W, 19.6 feet.
- S12°E, 21.3 feet.

A ponderosa pine marked "CN 1/16 S15 BT bears N20°E, 106.50 feet.

All bearing trees have a 6" red band painted around them and a Umatilla County Bearing Object sign attached.

Location & Comments: The corner falls on a steep East facing slope West of shallow draw, 1/2 mile south of the South Fork of the Walla Walla River.

Compass Declination:


19° East

Surveyor's Seal

Firm/Agency: Tomkins Land Surveying, Inc.
20 E. Poplar, Suite 204
Walla Walla WA 99362



Greg E. Flowers



Party Chief: Joshua R. Martin
Notes: Joshua R. Martin
Witness: Ryan Lowery

RENEWS 12/31/01

12/15/00

RECEIVED BY
Umatilla County Surveyor
Date 12-00
Rec'd By SM
No. 00-258-C