

OREGON CORNER RESTORATION FORM

Section: Corner common to sections 14, 13, 24 & 23

Township: 4N

Range: 37 EWM

County: Umatilla

Date: 12/01/99

Corner Designation: N-19

N-21

Previous Renewals/Surveys, etc.: This corner was originally set by U.S. Deputy surveyors, Charles L. and William C. Campbell, under Contract No. 733. Dated March 22, 1901. The Surveyor Generals notes state: "Set a pine post, 4 ft. long, 6 ins. Square, 24 ins. In the ground, struck rock and raised a mound of stone around for Cor. of Secs. 13, 14, 23 & 24, marked T4N S13 on N.E., R37E S24 on S.E., S23 on S.W. and S14 on N.W. faces, with 3 notches on S. and 1 notch on E. edges, from which:

A pine, 16 ins. Dia. Brs. N.40°W. 2.97 chs. Dist, marked T4N R37E S14 BT.

Raised a mound of stone 2 ft. base, 1 1/2 ft. high W. of cor., pits impracticable.

Monument(s) & Accessories Found (Condition & Source): Found the remains of a mound of stone 4 feet in diameter on a steep Westerly slope 25 feet South of the crest of a narrow ridge. A 27 inch down pine snag with visible scribing bears N41 1/2 ° W 167.3 feet to the stump hole.

Monument Detail: TOMKINS SURVEYING

T4N R37E

S14 S13

S23 S24

1999

WA 25893 OR 2360

Monument Set (Procedures & Description): At the location of the found mound of stone set a 5/8" x 30" iron rebar with a 2" aluminum cap marked as noted, 4" in the ground, struck rock. Erected a stone mound 4' in diameter 2' high around the monument.

New Accessories: A steel fence post with a land survey monument sign was placed 4' North of the corner.

A 15" Douglas fir bears N52°E 94.1 feet, marked T4N R37E S13 BT

A 18" ponderosa pine bears S88 1/2 °E 103.2 feet, marked T4N R37E S24 BT

A rock outcropping 3' high marked with an "X" 1 foot above ground bears S28 1/2 ° E 101.0 feet.

A 12" ponderosa pine bears N30 1/2 °W 125.2 feet, marked T4N R37E S14 BT

All bearing trees have a 6" red band painted around them and a Umatilla County Bearing Object sign attached, the "X" BO is painted red and has a Umatilla County Bearing Object sign attached.

Location & Comments: The corner falls on a steep narrow East West ridge East of Elbow Creek.

Compass Declination:


19° East

Surveyor's Seal


Firm/Agency: Tomkins Land Surveying, Inc.

20 E. Poplar, Suite 204

Walla Walla WA 99362



Greg E. Flowers



Party Chief: Greg E. Flowers

Notes: Greg E. Flowers

Witness: Bryan A. Martin

RECEIVED BY
Umatilla County Surveyor

Date 3-2000

Rec'd By KK

No. 00-39-R

RENEWS 12/31/01

3/01/00