

OREGON CORNER RESTORATION FORM

Section: 13

Township: 4 North

Range: 37 East, W.M.

County: Umatilla

Date: 08/06/2000

Corner Designation: K.5-25, South North 1/64 on the East line of Section 13

Previous Renewals/Surveys, etc.: None

Monument(s) & Accessories Found (Condition & Source): None.

Monument Detail: T4N

R37E R38E

S-N 1/64

S13 + S18

2000

LS 2820

Monument Set (Procedures & Description): At the position determined by survey set a 1"x 30" galvanized iron pipe 8" in the ground with a 2 1/2" brass cap attached. Surrounded with a mound of earth and stones to the top.

New Accessories: Set 6' carsonite post 5' South of the corner with survey monument and forest boundary stickers attached and a 6 foot steel fence post 5 feet West of the corner with a survey monument sign attached. Set 5/8"x30" rebar reference monuments (RM) with 1 1/2' aluminum caps stamped as shown, as follows:

N4°E 13.6 feet

S62°E 13.4 feet

S5°W 16.0 feet

N74°W 18.0 feet

All RM's are driven to refusal and surrounded with a mound of stone, and have a 6 foot steel fence post set alongside with bearing tree and survey monument signs attached.

Location & Comments: This corner is located on a barren, Southwesterly facing slope overlooking Tamarack Basin and is a considerable hike from the nearest road.

Compass Declination:

19° East

Firm/Agency: Tomkins Land Surveying, Inc.

20 E. Poplar, Suite 204

Walla Walla WA 99362

Party Chief: Josh Martin

Notes: Josh Martin

Witness: Ryan Laughery

Surveyor's Seal

REGISTERED PROFESSIONAL LAND SURVEYOR

Greg E. Flowers

OREGON JUNE 30, 1997 GREG E. FLOWERS 02820LS

RENEWS 12/31/01

RECEIVED BY

Umatilla County Surveyor

Date 12-00

Rec'd By SM

No. 00-254-C