

OREGON CORNER RESTORATION FORM

Section 21,28 Township 4N Range 37E W.M.
County Umatilla Date 8/1/93
Corner Designation: R-11

Previous Renewals/Surveys, etc. The original survey was made by George S. Pershin under contract No. 332, dated July 29th, 1879. He set a basalt stone, 14 x 12 x 4 on W. point of spur for 1/4 Sec. Cor.

A fir 10" in diam. bears N.53°W., 82 lks. dist.

A fir 20" in diam. bears S.36°W., 108 lks. dist.

Monument(s) & Accessories Found: (Condition and Source)

Found a basalt stone marked 1/4 on the south face in a mound of stone, and down and badly rotted fir with visible axe marks as per Land Corner Record Q-723. Corner falls on the W. point of spur.

Monument Detail:

T4N R37E

$\frac{1}{4}$

S21

S28

1993

OR 1106

Monument Set (Procedures and Description): Set a 1 1/2" x 30" iron pipe 12" in the ground with a mound of stone to the top with a 2 1/2" brass cap stamped as indicated in the monument detail. Set the stone beside the monument as a witness.

New Accessories: A 16" fir scribed T4N R37E S28 BT bears S.34 1/2°W., 44.6 ft.

A 17" fir scribed T4N R37E S21 BT bears N.10 1/2°W., 55.5 ft.

A rock out cropping 3' x 4' x 2' marked BO X 1' above ground bears N.55 1/2°E., 18.6 ft.

A 5/8" x 30" rebar set 24" in the ground with a plastic cap stamped WR WELLS PLS 1106 bears S.48°E., 24.5 ft.

A steel fence post with a Land Survey Monument sign attached brs. N. 3.8 ft.

Location & Comments: The corner falls on the W. point of a steep spur on the E. side of Couse Creek.

Compass Declination: 18° E

Firm/agency: Tomkins-Wells Joint Venture

Land Surveying

P.O. Box 1696

Pendleton, Oregon 97801

Surveyor's Seal

Party Chief: Greg Flowers

Notes: Greg Flowers

Witness: Todd Rosenbalm

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

expires 12-31-94

93-64-C