

OREGON CORNER RESTORATION FORM

Section 23,26 Township 4N Range 37E W.M.
County Umatilla Date 8/1/93
CORNER DESIGNATION: R-19

Previous Renewals/Surveys, etc. The original survey was made by George S. Pershin under contract No. 332, dated July 29th, 1879. He set a basalt stone 16 x 10 x 5 on N. E. face of spur for 1/4 Sec. Cor.
A fir, 18 ins. diam. brs. N.35°W., 55 lks. dist.
A fir, 13 ins. diam. brs. S.6°W., 27 lks. dist.
Charles L. & William C. Campbell retraced this survey under contract No. 733, dated March 22, 1901, and found the corner as described by Pershin they made no changes. Hambleton searched for the corner in 1977 but did not find it (map No. N-65).

Monument(s) & Accessories Found: (Condition and Source) Found a basalt stone 15 x 9 x 5 with 1/4 clearly marked on it laying loosely on the N. E. face of a spur a rotted stump bears S.6°W., 17.8 ft.. The tree that came from the stump we found 50' down the hill it had evidence of scribing on it.

Monument Detail:

T4N R37E
 $\frac{1}{4}$ $\frac{S23}{S26}$
1993
OR 1106

Monument Set (Procedures and Description): Set a 1 1/2" x 30" iron pipe with a 2 1/2" brass cap marked as indicated in the monument detail 14" in the ground with a mound of rocks to the top. Set the corner stone beside the monument as a witness.

New Accessories:

A 18" fir brs. N.77 1/2°E., 165.6 ft. marked T4N R37E S23 BT
A 18" fir brs. S.67°E., 81.4 ft marked T4N R37E S26 BT
A 17" fir brs. S.47 3/4°W., 53.6 ft marked T4N R37E S26 BT
A 20" fir brs. N.4°W., 68.2 ft. marked T4N R37E S23 BT
A steel fence post with a Land Survey Monument sign attached brs. N. 3.0 ft.

Location and comments: The corner is located on a relatively flat bench with very little brush on a steep N.E. side of a spur.

Compass Declination: 18° E

Surveyor's Seal

Firm/agency: Tomkins-Wells Joint Venture
Land Surveying
P.O. Box 1696
Pendleton, Oregon 97801

Party Chief: Greg Flowers
Notes: Greg Flowers
Witness: Todd Rosenbalm

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

expires 12-31-94

93-64-e