

OREGON CORNER RESTORATION FORM

Section 19,20,29,30 Township 4N Range 37E W.M.
County Umatilla Date 8/1/93
CORNER DESIGNATION: R-5

Previous Renewals/Surveys, etc. The original survey was made William Odell, under contract No.114, dated July 2nd, 1866. He set a post for Cor. for Secs. 19,20,29,& 30 from which:

A pine, 18 ins. diam. brs. S.54°W., 166 lks.
A pine, 36 ins. diam. brs. N.87°W., 136 lks.
A pine, 42 ins. diam. brs. N.40°E., 52 lks.
A pine, 36 ins. diam. brs. S.60°E., 116 lks.

In August, 1969 Donald Staebler set a 2" galv. pipe by double proportionate distance, from which:

A 12" pine, brs. N.16°E., 29.3 ft.
A 36" pine, brs. S.71°E., 33.2 ft.
A 18" pine, brs. S.62°W., 62.4 ft.

Per map filed with Umatilla County Surveyor No. F-25.

Monument(s) & Accessories Found: (Condition and Source)

Found 2" galv. pipe from which:

A 16" pine brs. N.15°E., 30.0 ft. marked S20 T4N R37E BT.
A 38" pine brs. S.72 1/2°E., 34.2 ft. visible scribing.
A 23" pine brs. S.61°W., 63.4 ft. with mostly healed blaze.
A 35" pine brs. N.88°W., 43.4 ft. with mostly healed blaze.

Monument Detail:

T4N R37E	
S19	S20
S30	S29
1993	
OR 1106	

Monument Set (Procedures and Description):

Set a 1 1/2" x 30" iron pipe with a 2 1/2" brass cap marked as described in the monument detail 18" in the ground with a mound of stone to the top.

New Accessories:

A steel fence post with Land Survey Monument sign attached brs. S. 3.5 ft.

Location & Comments: The corner is located on the level 15' E. of Basket Mtn. road.

Compass Declination: 18° E
Firm/agency: Tomkins-Wells Joint Venture
Land Surveying
P.O. Box 1696
Pendleton, Oregon 97801

Party Chief: Greg Flowers
Notes: Greg Flowers
Witness: Todd Rosenbalm

Surveyor's Seal

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Expires 12-31-94

9B-64-C