

**OREGON CORNER RESTORATION FORM**

Section 20,29 Township 4N Range R37E W.M.  
County Umatilla Date 8/1/93  
CORNER DESIGNATION: R-7

Previous Renewals/Surveys, etc. The original survey was made by William Odell, under contract No. 114, dated July 2nd, 1866. He set a post Cor. for 1/4 Sec.; from which,  
A fir, 18 ins. diam. brs. N. 5 lks.  
A fir, 20 ins. diam. brs. S.48°E., 11 lks.  
In 1969 Don Staebler found a 2" pipe and scribed 2 new BT's  
A 12" tamarack N.26°E., 25.7 ft.  
A 14" fir S.47°E., 43.7 ft.  
As shown on map of survey record No. F-25 Umatilla County records.

Monument(s) & Accessories Found: (Condition and Source) Found a 2" pipe that had been driven into the ground, from which a 9" dead tamarack brs. N.27°E., 25.7 ft. marked S20 T4N R37E BT.  
There was evidence of rotted wood to a depth of 20" where the pipe had been driven in.

**Monument Detail:**

T4N R37E  
1 S20  
4 S29  
1993  
OR 1106

Monument Set (Procedures and Description): Set a 1 1/2" x 30" iron pipe with a 2 1/2" brass cap marked as indicated in the monument detail, 24" in the ground, at the location of the 2" pipe. There were no rocks available for a rock mound.

**New Accessories:**

A 16" spruce brs. N.3°E., 19.4 ft. marked 1/4 S 20 BT  
A 9" fir brs. N.72 1/2°E., 41.1 ft. marked 1/4 S20 BT  
A 14" fir brs. S.14°E., 39.7 ft. marked 1/4 S29 BT  
A 8" spruce brs. S.41°W., 30.6 ft. marked 1/4 S29 BT  
A steel post with Land Survey Marker sign attached brs. N. 3.2 ft.

Location & Comments: The corner is located in the timber on level ground the area has been logged several times.

Compass Declination: 18° E  
Firm/agency: Tomkins-Wells Joint Venture  
Land Surveying  
P.O. Box 1696  
Pendleton, Oregon 97801

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Party Chief: Greg Flowers  
Notes: Greg Flowers  
Witness: Todd Rosenbalm

93-64-c

expires 12-31-94