

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 37E. , W.M.

Corner Code No. V-7
Note: Monument marked as shown below


History of original corner establishment:

This corner was originally established by W.H. Odell, U.S. Deputy Surveyor, under Contract No. 114, dated July 2, 1866.

The original notes state:

Set post corner for 1/4 section from which:

A larch 20 in dia bears N 20° W 22 links.
A larch 18 in dia bears S 25° E 30 links.



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

Found a 22 by 10 by 6" basalt stone set 18 " in the ground in a East-West fence line, from which:

A 10" western larch, with scribing visible on partly healed blaze, bears S 03 1/2° W 27.4'. This tree is cut off above the scribing. No record of this tree was found in County Records.

Description of monument and accessories I established to perpetuate the original location of this corner:

The origin of the found stone is not known, but it has been used on all recent surveys in this area. I accept the stone as the perpetuation of the original corner monument.

At the position of the found stone, set a 2 1/2" brass cap, on 1 1/4" by 30" galvanized iron pipe, 24" in the ground and surrounded with a mound of earth. Placed the found stone on the North side of the new monument.

Marked 4 New bearing trees:

A 8" douglas fir bears N 38° E 18.8' scribed 1/4 S29 BT.
A 7" western larch bears S 77 1/2° E 38.6' scribed 1/4 S32 BT.
A 8" western larch bears S 81 1/2° W 14.6' scribed 1/4 S32 BT.
A 10" Englemann spruce bears S 01° W 26.1' scribed 1/4 S32 BT.

Placed bearing object signs on the new bearing trees.

Set steel fence post West of corner and attached witness corner sign.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date 9-91
Rec'd By JK
No. 91-75-C

★ GPO—798-276