

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

**T 4N, R 37E. , W.M.**

**Corner Code No. V-9**  
 Note: Monument marked as shown below


**History of original corner establishment:**

This corner was originally established by W. H. Odell, U.S. Deputy Surveyor, under Contract No. 714, dated July 2, 1866.

The original notes state: Set post corner for sections 28, 29, 32 & 33 from which:

- A fir 8 in dia bears S 68°W 27 links.
- A fir 8 in dia bears S 75°E 21 links.
- A fir 20 in dia bears N 30°W 32 links.
- A fir 8 in dia bears N 20°E 56 links.

This corner was declared lost and was re-established by double proportion measurement by Douglas M. Ferguson in 1978 as shown on Survey No. P-113-B & corner certificate No. G-728.



Corner No.  
Compass Declination: 18.0°

**Description of corner evidence found:**

Found 2 1/2" brass cap on a 2 1/2" galvanized iron pipe protruding 2" from the ground from which:

- A 10" douglas fir stub, 6 feet high bears S 37°W, 48.9' with partly healed blaze.
- A 8" Englemann spruce bears N 86°W, 61.1' with partly healed blaze.
- A 18" Englemann spruce bears N 26°E, 33.7' with partly healed blaze.

The bearing trees noted above were marked by Douglas M. Ferguson. The NE & NW bearing trees have USFS bearing tree tags attached.

**Description of monument and accessories I established to perpetuate the original location of this corner:**

Maintained corner by clearing brush out from around the corner monument. Set steel fence post South of corner and attached witness corner sign.

Marked two additional bearing trees:

- A 10" Englemann spruce bears N 50°W, 62.6' scribed T4N R37E S29 BT.
- A 19" Englemann spruce bears S 49 1/2°W, 57.5' scribed T4N R37E S32 BT.

Placed bearing object signs on the new bearing trees.

There is no nearby tree for reference in the Southeast quadrant.

REGISTERED PROFESSIONAL LAND SURVEYOR
<i>William R. Wells</i>
OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of..... County of.....  
 State of....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.....  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

**RECEIVED BY**  
 Umatilla County Surveyor  
 Date 9-91  
 Rec'd By AK  
 No. 97-75-C