

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 37E., W.M.

Corner Code No. X-17

Notes: Monument marked as shown below


History of original corner establishment:

This corner was originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 332, dated July 29, 1879.

The original notes state:

Set fir post on slight North slope for 1/4 sec. cor.

A spruce 1 1/2 in. di. brs S 43° E 6 lks dist.  
A spruce 6 in. di. brs S 28° W 15 lks dist.



Corner No.  
Compass Declination: 18.0°

Description of corner evidence found:

Found 1 3/4" O.D. iron pipe with top 2" below ground. This monument has been used as the perpetuation of the original 1/4 corner location on all recent surveys in the area. See corner certificate No. Q-734 and Survey Map No. R-149-B.

A 5/8" smooth iron pin with a 1 1/2" Oregon State Highway alum. cap bears N 27°W, 1.21' from the recovered iron pipe. I find no record for the establishment of the State Highway Division monument.

Description of monument and accessories established to perpetuate the original location of this corner:

At the position of the found 1 3/4" O.D. iron pipe, I set a 2 1/2" brass cap on 1 1/4" by 30" galvanized iron pipe, 24" in the ground and surrounded with a mound of earth and stone. Buried the iron pipe on the SW side of the new monument.

Referenced the new corner monument as follows:

A 12" Englemann spruce bears N 33 1/2° E 18.3' scribed 1/4 S35 BT.  
A 12" Englemann spruce bears S 26 1/2° E 43.7' scribed 1/4 S35 BT.

Placed bearing object signs on new bearing trees noted above.

The SE corner of a recently constructed cabin bears S 49 1/2° W 51.0'.  
A brass washer, stamped "PLS 1106", nailed to the South side of a 18" Englemann spruce, 6" above ground bears N 45° W 31.4'.

Set steel fence post South of corner and attached witness corner sign.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of..... County of.....  
State of....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19....  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
Umatilla County Surveyor  
Date 9-9-77  
Rec'd By RK  
No. 91-75-C

☆ GPO-788-276