


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

The original survey was made by George S. Pershin under contract No 332, dated July 29, 1879. He set a fir post on slight North slope for $\frac{1}{4}$ sec. cor. He set the following bearing trees:

A spruce 11" dia. bears S 43 E, 6 lks. dist.
A spruce 6" dia. bears S 28 W, 15 lks. dist.



Description of corner evidence found:

I found no trace of the original post nor the bearing trees, however I did find a $1\frac{1}{4}$ " iron pipe at the $\frac{1}{4}$ corner location; the iron pipe being harmonious to the topography call in the original GLO notes, I tied the position of this iron pipe to my co-ordinate system and even though I found no record of this iron pipe being set, there is evidence that it is being used as the $\frac{1}{4}$ corner and the collateral evidence helps to confirm its position thus I accepted it as the perpetuation of the original $\frac{1}{4}$ corner and continued with my retracement survey.

Description of monument and accessories I established to perpetuate the original location of this corner

None

REGISTERED
PROFESSIONAL
LAND SURVEYOR



OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848

Office of County of

State of, I hereby certify that the within instrument was filed in this office for record on the day of

..... by

(COUNTY OFFICIAL) (DEPUTY)