

ERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 37E. , W.M.

Corner Code No. Z-11

Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by George S. Pershin, U.S. Deputy Survey, under Contract No. 304, dated September 19, 1878.


The original notes state:

Set Fir post on level for 1/4 Sec. Cor. from which:

A tamarack, 22 in. di. brs N 30°E 10 lks. dist.

A fir, 6 in. di. brs S 65°W 11 lks. dist.

This corner was re-established by single proportion measurement by Douglas M. Ferguson in 1978, as noted on corner certificate G-736.



Corner No.

Compass Declination: 18.0°

Description of corner evidence found:

Found 2 1/2" brass cap on 2 1/2" galvanized iron pipe protruding 4" from the ground from which:

A 15" douglas fir bears N 52°E 60.55' with healed blaze.

A 15" white fir bears S 65°W 40.66' with partly healed blaze.

The bearing trees noted above were marked by Douglas M. Ferguson in 1978. The trees have USFS bearing tree tags attached.

Description of monument and accessories established to perpetuate the original location of this corner:

Maintained existing monument by cleaning up debris around it. Set steel fence post East of corner and attached witness corner sign.

Marked two new bearing trees:

A 9" douglas fir bears N 46°W 27.7' scribed 1/4 S33 BT.

A 9" western larch bears N 32 1/2°E 31.6' scribed 1/4 S33 BT.

Attached bearing object signs to the new bearing trees.

REGISTERED

PROFESSIONAL

LAND SURVEYOR

Will: R. Wells

OREGON

JULY 22, 1977

WILLIAM R. WELLS

1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19....

..... by

(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 9-91

Rec'd By KK

No: 91-25-C

☆ GPO-798-276